

SURVEY & REMONUMENTATION

NOV 25 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Oshtemo Twp.

Located In:	Corner Code #
<u>Kalamazoo</u> (County)	
1. Public Land Survey	T 2S R 12W H-05
	T R
	T R
	T R
2. Property Controlling in Section	S T R
	S T R
3. Miscellaneous Property in Sec.	S T R
	S T R

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

98 OCT 22 AM 11 37

CLERK - REGISTER

LIBER 2 PAGE 350

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on March 23 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4			3		2			1
3													
4	7		8		9			10		11			12
5													
6	18		17		16			15		14			13
7													
8	19		20		21			22		23			24
9													
10	30		29		28			27		26			25
11													
12	31		32		33			34		35			36
13													

A. Description of original monument and accessories and/or subsequent restoration:

1829: United States Government Surveyors; set 1/4 Section post.

Hickory 3" N. 21⁰ E. 157 lks.
W. Oak 8" S. 58⁰ W. 76 lks.

1865: F. Stimson, County Surveyor; monument not described.

Wh. Oak 18" S. 78⁰ W. 102 lks.
Wh. Oak 20" N. 17^{1/2} W. 56 lks.

1875: E. Strong, County Surveyor; stake and stone around from 1 U.S. (witness).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1893: E. Strong, County Surveyor; found stake and stones of record. Set new stake. 1 U.S., and Co. B.T. good.

1998: Found 4 stones around stake print. Stake print good to 2' deep. 4 stones formed a 2" dia. hole just below surface. Stones were 7"x6"x3 1/2", 7"x6"x6", 6"x6"x6" and 6"x6"x6". Noted 11" square fence post East 6:6' and in line with fence to West.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-05: South 1/4 post, Section 10, T. 2 S., R. 12 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on April 16, 1998 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 4 stones around a stake print as described by E. Strong, County Surveyor in 1875 & 1893 surveys. Placed 30" Harrison monument in stake print and placed stones around in the same relative position as they were found.

Exist. Double Head Nail in North Side	16" Oak	S. 88 ⁰ E.	40.49'
Exist. Double Head Nail in North Side	16" Locust	S. 60 ⁰ E.	23.07'
Exist. Double Head Nil in East Side	18" Oak	S. 08 ⁰ E.	27.45'
PK Nail in East Side	6" Oak	N. 30 ⁰ E.	30.63'

Signed by Robert E. Snell

Surveyor's Michigan License No. 9734

Date 10-22-98