

**SURVEY &
REMONUMENTATION**

1 JUL 23 1997

LIBER 2 PAGE 137

2 COMMISSION
Oshtemo Twp.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

CLERK - REGISTER

Handwritten signature

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
97 MAY 16 PM 3 50

For corners in Kalamazoo Located In: _____ Corner Code # _____
(County)

1. Public Land Survey	T	<u>2S.</u>	R	<u>12W.</u>	<u>H-9</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Section	S	_____	T	_____	R
	S	_____	T	_____	R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	6	5	4	3	2	1					
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen, in a field survey on March 21, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1830 - George Harrison, D.S., "Set 1/4 Section post", Wh. Oak 15" N. 45° E. 74 lks., B. Oak 3" S. 01° E. 16 lks.
1864 - F. Stimson, C.S., "Stone by former survey"

1976 - Ingersoll, Watson & McMachen, Inc., "Found pointed stone and drag tooth, 2' West of fence North and 3' South of fence West. Set 2" pipe 3' high beside it. 12" Oak S. 85° W. 54.17', 24" Oak N. 15° E. 18.96', 8" Hickory East 28.82'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found pointed stone with drag tooth per 1976 witnesses.

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
4-16-1997**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found Pointed Stone is accepted as a careful and faithful perpetuation of the position of the original corner. Replaced stone with Standard Harrison Monument, Accessories:

- Nail & Tab in West side 30" Oak N. 15° E. 18.90'
- Nail & Tab in East side 4" Twin Cherry S. 30° W. 20.80'
- Nail & Tab in North side 24" Oak S. 80° W. 53.60'
- Nail & Tab in North side 16" Hickory N. 80° E. 28.77'



Handwritten initials R.E.S.

Signed by Allen H. McMachen
Surveyor's Michigan License No. 16935

Date 5/15/97