

SURVEY & REMONUMENTATION

JUL 23 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Oshtemo Twp.
Kalamazoo
 (County)

Located In:

Corner Code #

- | | | | | | |
|--------------------------------------|---|------------|---|-------------|-------------|
| 1. Public Land Survey | T | <u>2S.</u> | R | <u>12W.</u> | <u>H-11</u> |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | | |
| | S | | T | | |
| 3. Miscellaneous Property in Section | S | | T | | |
| | S | | T | | |

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Allen H. McMachen, in a field survey on March 21, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1830 - George Harrison, D.S., "Set 1/4 Section post", Bl. Oak 12" N. 27° E. 58 lks., Bl. Oak 10" N. 50° W. 45 lks.

1974 - Ingersoll, Watson & McMachen, Inc., "Found pointed stone, 30" Oak West 12.6', 20" Oak N. 10° E. 35.60', 18" Oak N. 50° E. 11.87' " Meas. West 2626.12' to Southwest corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found pointed stone (±70 lb.) in tree row per 1974 witnesses. Stone is ±1312' West of West line of Plat of LaSalle Homesites #1, L. 36, Pg. 19.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found Pointed Stone is accepted as a careful and faithful perpetuation of the position of the original corner. Replaced stone with Standard Harrison Monument, Accessories:

- "PK" Nail in East side 8" Sassafras N. 15° E. 26.60'
- "PK" Nail (found) in S.W. side 6" Sassafras S. 50° E. 18.80'
- "PK" Nail (found) in West side 6" Hickory S. 05° W. 19.30'
- "PK" Nail (found) in North side 36" Oak N. 10° W. 12.60'



Signed by Allen H. McMachen
 Surveyor's Michigan License No. 16935

Date 5/15/97

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 97 MAY 16 PM 3 50
 Clerk - Register
 [Signature]

LIBER 2 PAGE 135

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												