

SURVEY & REMONUMENTATION

1 OCT 06 1997
2 COMMISSION

LIBER 2 PAGE 171

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
97 JUL 29 PM 3 57
J. J. Johnson
CLERK - REGISTER

For corners in Township of Oshtemo
Kalamazoo (County) Located In: Corner Code #

1. Public Land Survey	T	2S.	R	12W.	I-3
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____
- 6. IWM Job No. 26050

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen, in a field survey on April 14, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1830 - George W. Harrison, D.S., Set post corner to Sections 2, 3, 10 and 11, Blk. Oak 4" N. 74° E. 30 lks., Blk. Oak 4" N. 79½° W. 53 lks.
1871 - F. Hodgman, C.S., Section corner lost. Re-established midway between quarter Section corners North and South and from testimony of old residents in the centerline of fences built on line while the original corner was good. Planted post, stone and brick. Y. Oak 4" S. 8° E. 45½ lks. (30.03') Br. Oak 12" N. _____ W 166 lks. (109.56')
NOTE: A proportional division between the quarter Section corners East and West adjacent to this corner would locate it 26 lks (17.16') farther West

1951 - Wilkins & Wheaton Co. Surveyor, N.W. corner - lost- replaced in line with fence to North and fence to South and at bisection of mile between West quarter corner, Section 11 and West quarter corner Section 2 and with the testament of long time residents. Measured 2646.08' between West quarter corner and Northwest corner. Measured 2620.09 feet between Northwest corner and North quarter corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found ½" iron in mon. box. 7" below pavement. Excavated to depth of 4' into virgin sand and found no additional evidence of corner. Measured East 2619.84' and meas. South 2643.76'

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
6-19-1997
R. S. S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found iron is accepted as a careful and faithful reestablishment of the position of the original corner.
Accessories:

- Nail & Tab in South side 10" Ash N. 65° E. 59.68'
- Nail & Tab in Northeast side 30" Wh. Oak S. 44° E. 43.51'
- Nail & Tab in South side 28" Oak N. 70° W. 61.21'
- Nail & Tab in East side 18" Walnut N. 35° W. 36.25'



Signed by Allen H. McMachen
Surveyor's Michigan License No. 16935

Date 7/14/97