

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PC 998

CLERK - REGISTER
Jamison Strong

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
SEP 10 PM 1 21 '93

Register of Deeds Stamp & File Number

For corners in

Kalamazoo

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 2 S R 12 W I-7
Sec. Cor. 14, 15, 22, 23 T 2 S R 12 W I-7
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Robert E. Snell, in a field survey on June 11, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- I-7 Government post set 1829.
- Ed Strong 1865: "Witness stumps standing, set stone".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I-7 July 7, 1993: Found iron in monument box in roadway.
Removed box and iron and found stone set by Strong.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-7 July 7, 1993: Accepted stone and iron as a careful and faithful perpetuation of the position of the original corner and placed an 18" Harrison Monument over stone and replaced monument box in roadway.

- Witness
- 1. Tab/PK nail 36" Maple - S. 45° W. 37 ft.
 - 2. Tab/PK nail SE corner Old Oshtemo Township Hall - N. 49° W. 80.6 ft.
 - 3. PK nail 40" White Oak - N. 20° W. 98.95 ft.
 - 4. Tab/PK nail 8"-8"-6" Triple Elm - N. 31° E. 53.61 ft.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
5-20-93

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Signed by

Robert E. Snell
9734

Date

Sept. 9-93

Surveyor's Michigan License No.