

SURVEY & REMONUMENTATION

AUG 22 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

'95 APR 26 AM 11 09

Signature of Clerk-Register

CLERK-REGISTER

LIBER 1 1290

Register of Deeds Stamp & File Number

For corners in

Kalamazoo

(County)

Located In:

Corner Code #

Oshtemo Township

1. Public Land Survey

T 2 S R 12 W

I-8

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous

S T R

Property in Sec.

S T R

4. Lot No. , Recorded Plat

5. Private Claims

Grid table with columns A-L and rows 1-13. A star symbol is located at the intersection of row 8 and column J.

I, Robert E. Snell, in a field survey on July 13, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1829: U.S. Government Survey; Set 1/4 Section Post.

Black Oak 3" North 45 1/2° West 49 Lks

Black Oak 4" North 80 1/2° East 75 Lks

1906: Ed Strong, County Surveyor; West 1/4, stone with one brick coming to 3" of the surface, in line with opposite fence corners.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found iron in monument box in centerline of intersection. Dug to a depth of 4'±. Found a stone with drill hole and one brick on end, 2.53' West of iron. More digging resulted in finding remains of stake remains, 0.75' North and 0.65' East of stone and brick and below it.

RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP 4-20-95

Signature of Peer Group member

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-8 West 1/4 Post Section 23, T. 2 S., R. 12 W., Ratified by the Kalamazoo County Remonumentati Program Peer Group on April 20, 1995. Found stone and brick as called for by Ed Strong, County Surveyor, in a survey dated 1906 near remains of original corner as set by original U.S. Government Survey dated 1829. The stake remains are accepted as a careful and faithful perpetuation of the original position of the corner. Placed a 20" Harrison monument and monument box over remains of stake.

PK Nail in Southeast Side of Power Pole North 42° East 84.90'
PK Nail in Northeast Side of Power Pole North 38° West 62.91'
PK Nail in North Side of 32" Maple South 68° East 90.89'
Exist. Nail/Tab in Southeast Side of Power Pole South 43° West 41.61'

Signed by Robert E. Snell

Date 4-26-95

Surveyor's Michigan License No. 9734