

SURVEY & REMONUMENTATION

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Kalamazoo</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>2 S</u> R <u>12 W</u>	<u>I-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 '94 JUN 21 AM 8 56
Jessie [Signature]
 CLERK - REGISTER

LIBER 1 PG 1092
Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on December 8, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Established by U.S. Government Survey 1829 - Set Post
 Bl. Oak 12" South 84°-E 67 Lks (44.22')
 Wh. Oak 8" North 89°-W 74 Lks (48.84')
 1875-E. Strong County Surveyor - "T" Rail from U.S. Stump.
 1962-Wilkins & Wheaton Engr. Co. - plow point.
 1962-MSHD-Found 8" R.R. anchor plate - plow point.
 1968-Wilkins & Wheaton Engr. Co.-found rust remains of "T" Rail, placed 3/4"x3' iron & 1/2"x18" iron rod.
 Iron-N 3°-13' E 33.53' 10" Oak-S 08°-25' E 18.5' 10" Oak-S 79°-24' E 25.35'
 24" Oak-N 40°-51' W 30.10' Twin 8&10" Oak-S 30°-06' W 27.2'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found R.R. anchor plate and 1/2"x18" iron near surface, recovered 3/4"x3' iron and rust remains of "T" rail as called for in previous surveys below surface iron. Original corner not recovered.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
12/16/93

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-12 West 1/4 post Section 35, T. 2 S., R. 12 W., Ratified by Kalamazoo County Remonumentation Program Peer Group on December 16, 1993. Found 1/2"x18" iron and R.R. anchor plate near surface and found 3/4"x3' iron below and is accepted as a careful and faithful perpetuation of the position of the original corner. Removed 1/2"x18" iron and R.R. anchor plate as well as 3/4"x3' iron, placed 30" Harrison monument and placed R.R. anchor plate along side of monument.

- PK Nail in E side 9" Sassafras N 14°-30' W 1.55'
- PK Nail in SW side 30" Oak N 38° W 29.95'
- PK Nail in SW side 16" Oak S 76° E 25.25'
- PK Nail in E side 18" Oak S 08° E 18.20'
- PK Nail in W side 22" Oak N 36°-30' E 53.68'

Signed by Top of R.R. cut South 12.5' Date 1-20-94

Surveyor's Michigan License No. 9734