

SURVEY &
REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

AUG 22 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

APR 26 AM 11 09

For corners in

Kalamazoo COMMISSION
(County)

Located In:

Corner Code #

Oshtemo Township
1. Public Land Survey

T 2 S R 12 W

I-13

T R

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

James J. ...

CLERK-REGISTER

LIBER

1 1291

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert E. Snell, in a field survey on January 31, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1827: U.S. Government Survey; Set Corner to Sections 34 and 35.

Wh. Oak 13" North 27° West 120 Lks
Burr Oak 8" North 30½° East 90 Lks

1875: Ed Strong, County Surveyor; Very large stone and crockery from tree and stump of U.S.

1960: Robert E. Snell, County Surveyor; Found stone disturbed. Placed iron 138.54' West of Northeast Corner, Section 3, as called for in Ed Strong 1875 survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Placed 20" Harrison monument in line produced from South 1/4 Post of Section 35, Oshtemo Township (J-13) over Northeast Corner of Section 3, Texas Township (I-1), 138.54' West of the Northeast Corner of Section 3, Texas Township.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
4-20-95

R.E.S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13 Southeast Corner Section 34, T. 2 S., R. 12 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on April 20, 1995, and is accepted as a careful and faithful re-establishment of the position of the original corner. Placed a 20" Harrison monument in monument box after road reconstruction was completed.

CL Hydrant North 72° East 72.4'
PK Nail in Northwest Side (3' high) Power Pole South 70° East 113.90'
CL Manhole Cover South 64° West 11.10'
1/2 Iron Rod in Concrete (Plat Monument) North 02° East 50.10'

Signed by *Robert E. Snell*
Surveyor's Michigan License No. 9734

Date April 25, 1995