



LC-000068
Page: 1 of 1
11/18/1999 02:22P
Bk-2 Pg-521

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &
REMONUMENTATION

For corners in

Form with fields for County (Kalamazoo), Township (Oshtemo), and survey details (Public Land Survey, Property Controlling, etc.)

FEB 08 2000

SECTION

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column J and row 3.

I, Gary D. Hahn, in a field survey on August 18, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules...

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- List of survey points and monuments: 1829 - Corner established by U.S. Deputy Surveyor George W. Harrison... 1871 - F. Hodgman... 1851 - Wilkins & Wheaton... 1974 - L.C.R.C. Liber 1, Page 730... 1979 - Acro Engineering... 1993 - L.C.R.C., Liber 1, Page 1006... 1995 - L.C.R.C., Liber 1, Page 1323...

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original monument and accessories not recovered. Found a 5/8" diameter 18" long rod in the asphalt road 1.6' south of road centerline. Removed rod and found an 8" x 11" x 16" pointed stone surrounded by brick directly below the surface iron.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-3, North Quarter Post Section 11, Town 2 South, Range 12 West, ratified by Kalamazoo County Remonumentation Peer Group on September 23, 1999. The position of the found stone is accepted as a careful and faithful perpetuation of the position of the original corner.

Witness Ties:

- 1/2" diameter rebar S 2° W 50.00'
Set Mag nail in West side of 6" Oak N 22° E 34.22'
Set 1/2" rebar next to metal culvert S 46° W 34.03'
Set 1/2" rebar next to metal culvert S 58° E 45.04'
1/2" diameter rebar S 2° W 100.00'

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
9-23-1999



Signed by [Signature]
Surveyor's Michigan License No. 38116

Date 11/8/99

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS,

JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983 REVISED OCT., 1995