

FEB 18 1994

1 - COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
1993 SEP 10 PM 1 21  
1 PG 997  
CLERK - REGISTER  
LIBER

For corners in	Located In:	Corner Code #
Kalamazoo (County)		
1. Public Land Survey	T 2 S R 12 W	J-7
¼ Sec. Cor. 14, 23	T 2 S R 12 W	J-7
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert E. Snell, in a field survey on August 27, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- J-7 Government post set December 1829.
- Ed Strong 1883: S. ¼ on corner fence post, stump good.
- 1961 Ingersoll set iron rod for S. ¼ post at bisection of S. line of Section 14.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- J-7 Found iron rod set by Ingersoll in 1961 from Ingersoll witness.
- Witness: RR tie fence post N. 85° E. 2.1 feet.

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
**5-20-93**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- The iron placed by Ingersoll is accepted as the best available evidence of the original corner position and the iron was replaced with a 30" Harrison Monument.
- Witness
1. Tab/PK nail in 8" multiple (6) Wild Cherry - W. 19.12 ft.
  2. Tab/PK nail in RR tie fence corner - N. 70° E. 2.18 ft.
  3. Tab/PK nail in 12" Oak - N. 75° E. 10.74 ft.
  4. 24" Wild Cherry - N. 10° E. 64.24 ft.

Signed by Robert E. Snell  
Surveyor's Michigan License No. 9734

Date Sept 9 - 93