

1995  
SECTION

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

'55 AUG 25 PM 3 51

For corners in  
Kalamazoo  
(County)

Located In:	Corner Code #
T <u>2</u> S R <u>12</u> W	J-9
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

*James J. Jones*  
CLERK-REGISTER

LIBER **1 1336**  
Register of Deeds Stamp & File Number

- Oshtemo Township  
1. Public Land Survey  
2. Property Controlling in Section  
3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert E. Snell, in a field survey on June 10, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9					☉								
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1829: United States Government Surveyors; Set 1/4 Section Post.

- Wh. Oak 6" North 08° East 33 Lks
- Wh. Oak 4" South 03° West 9 Lks

1874: Ed Strong, County Surveyor; U.S. Stump [found]

- Wh. Oak 12" North 64° West 107 Lks

1897: Ed Strong, County Surveyor; Found sonthe from two trees.

- Wh. Oak 8" South 72° East 73½ Lks
- Y. Oak 8" North 61° East 65 Lks

1908: Ed Strong, County Surveyor; Found drilled stone  
W.Oak 12" N 64° W

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Y.Oak 16" N 45° ± E 104 Lks  
16 Lks

1994: Found iron in Monument Box. Iron was 3/8" x 18" and 4" below surface. Below iron found stone (12" x 9" x 8") with four smaller stones around. Noted no discernible marking on stone.

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
5-18-95 *R.E.S.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-9 North 1/4 Post Section 26, T. 2 S., R. 12 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on May 18, 1995 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found stone (12" x 9" x 8") with four smaller stones around below 3/8" x 18" Iron in monument box. Stone was called for in surveys by Ed Strong in 1874, 1897, and 1908. Placed 16" of 20" Harrison monument over stone with monument box over.

Found Nail in North Side	20" Oak	South 72° East	38.61'	In Centerline of Southbound Lane of 9th Street
PK Nail in West Side	24" Oak	North 43° East	67.28'	
PK Nail in West Side	Light Pole	North 18° West	61.56'	
Found Nail in South Side	34" Oak	South 80° West	22.24'	

Signed by *Robert E. Snell*  
Surveyor's Michigan License No. 9734

Date 8-22-95