

SURVEY  
REMONUMENTATION

AUG 2 2 1995

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

'95 APR 26 AM 11 09

For corners in COMMISSION

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
<u>Oshtemo Township</u>		
1. Public Land Survey	T <u>2</u> S R <u>12</u> W	<u>J-11</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*James J. Jones*  
CLERK-REGISTER

LIBER 1 ■ 1292

Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on June 10, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1829: U.S. Government Survey; Set 1/4 Section Post.  
Bl. Oak 9" North 05° East 7 Lks  
W. Oak 5" South 61 1/2° East 24 Lks
- 1874: Ed Strong, County Surveyor; Iron and stone of former survey  
Sugar 5" South 58° East 47 Lks  
Sugar 5" North 64° East 48 Lks

1928: Kalamazoo County Road Commission; South 1/4 Post Section 26, iron stake (field notes)  
Maple 18" S 30° E 52.9' Maple 6" S 30° W 56.3' Walnut 14" S 80° E 80.8'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found 3/8" x 18" iron in monument box. Below this iron was found an older 1/2" x 12" iron. Dug a 4' x 4' hole to a depth of 4' and found nothing futher. Dug to about 7' with post hole digger and found no other evidence.

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
4-20-95 *R.E.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-11 South 1/4 Post Section 25, T. 2 S., R. 11 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on April 20, 1995. Found 1/2" x 12" iron 2 1/2' below surface and is accepted as a careful and faithful reestablishment of the position of the original corner. Placed a 20" Harrison monument and monument box in place of iron.

Exist. PK Nail in North Side	14" Maple	North 64° West	49.32'
Exist. Nail/Tab in	Telephone Pole	South 58° West	50.35'
PK Nail in Southeast Side of	Power Pole	South 32° West	93.13'
Nail in Southwest corner of	Concrete Light Pole Base	South 80° East	50.34'

Signed by *Robert E. Snell* Date 4-26-95  
Surveyor's Michigan License No. 9734