

AUG 22 1995

LAND CORNER REGORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

'95 APR 26 AM 11 09

For corners in COMMISSION

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
<u>Oshtemo Township</u>	<u>T 2 S R 12 W</u>	<u>J-12</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

James J. Jones

CLERK-REGISTER

LIBER 1 1293

Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on August 24, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
This position not established by original government surveyors.

1962: Wilkins & Wheaton Engineering Company; Center 1/4 Post by Intersection (placed).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Re-established Center 1/4 Post by intersection of 1/4 Lines from previously ratified Section Posts. Set PK Nail.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
4-20-95

R. E. Snell

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-12 Center of Section 35, T. 2 S., R. 12 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on April 20, 1995. Placed a PK Nail at the intersection of 1/4 Lines. This position not established by original government surveyors. Monument placed by Kalamazoo County Road Commission and the monument is accepted as the best available evidence of the position of the corner.

- PK Nail in West Side of Power Pole North 30° West 106.67'
- PK Nail in West Side of Power Pole North 40° East 116.02'
- PK Nail in South Side of Triple Mulberry South 60° West 95.55'
- PK Nail in Southwest Side of 19" Pine North 58° West 64.15'

Signed by *Robert E. Snell*

Date 4-26-95

Surveyor's Michigan License No. 9734