

SURVEY & REMONUMENTATION

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Kalamazoo (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>2</u> S R <u>12</u> W	K-12
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 94 JUN 21 AM 8 56
 Clerk-Register

LIBER 1 PG 1094
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert E. Snell, in a field survey on December 9, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner post established by U.S. Government Survey 1827-William Brookfield
 Accessories: Wh. Oak 15" S 26½° E 258 Lks (170.28')
 Bl. Oak 12" N 5° W 248 Lks (163.68')
 1962-Wilkins & Wheaton Engr. Co.-Placed iron on bisection of NE & SE corner.
 1978-John Stack-Reset from Wilkins & Wheaton survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2"x18" iron rod at surface, found 1/2"x18" iron rod and remains of rotted lath at 1½' depth and 0.06' W of surface iron, found stone 6"x5"x6" with flat bottom and chipped rounded top at 3' depth. Shaved undisturbed soil under stone and found 2"x2" dark evidence of old stake 0.37' West and 0.03' North of surface iron.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
 12/16/93

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-12 East 1/4 post Section 35, T. 2 S., R. 12 W., Ratified by Kalamazoo County Remonumentation Program Peer Group on December 16, 1993. Found 1/2" iron over 1/2" iron 0.37' East and 0.03' South of stone with stake remains below and is accepted as the best available evidence of the position of the original corner. Removed both irons and placed 30" Harrison monument over stake evidence and stone and replaced surface iron.

PK Nail in S side	30" Wild Cherry	N 82°-30' W	83.98'
Nail/Tab (exist.) W side	12" Triple Wild Cherry	N 05° E	8.02'
SE corner of steel elect. tower		N 23° E	325.07'
NW corner of steel elect. tower		S 07° E	437.1'

Signed by Robert E. Snell Date 1-20-94
 Surveyor's Michigan License No. 9734