

SURVEY & REMONUMENTATION

AUG 22 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

95 APR 26 AM 11 09

For corners in

Kalamazoo
(County)

Located In:

Corner Code #

Oshtemo Township

T 2 S R 12 W

K-13

1. Public Land Survey

T R

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

James J. Jones

CLERK-REGISTER

LIBER 1 1294

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert E. Snell, in a field survey on January 12, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1827: U.S. Government Survey; Set Post Corner Sections 35 and 36.

Wh. Oak	4"	North	25 1/2°	West	84 Lks
Wh. Oak	9"	North	29°	West	32 Lks

1962: Wilkins & Wheaton Engineering Company; Found State Cap (no information in State Office)

1992: Wilkins & Wheaton Engineering Company; Found large iron (1 1/2").

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993: Replaced Southeast Corner of Section 35 from witnesses following sewer and road reconstruction. Original Corner lost in sewer construction.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
12-16-93 *R.E.S.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13 Southeast Corner Section 35, T. 2 S., R. 12 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on December 16, 1993. Found iron in monument box as replaced following sewer construction and is accepted as a careful and faithful perpetuation of the position of the original Corner. Placed a 20" Harrison monument in monument box.

Monument in Monument Box (K-1; T. 3 S., R. 12 W.)	East	63.37'
Nail/Tab (MSHD BM) in Southwest Side	North 21° East	27.95'
Nail/Tab (MSHD) in North Side	South 77° East	140.13'
Nail/Tab (MSHD BM) in North Side	South 12° East	23.10'
60d Spike in South Side	North 72° West	85.18'

Signed by *Robert E. Snell*
Surveyor's Michigan License No. 9734

Date 4-26-95