

APR 01 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

'95 DEC 8 AM 10 55

James Young
CLERK-REGISTER

LIBER 1 1399

Register of Deeds Stamp & File Number

Form with fields: For corners in KALAMAZOO (County), Located In: OSHTEMO TWP., Corner Code #: L2. Includes a table for recording corners with columns for Town, Range, and Section.

Grid table with columns A-M and rows 1-13. A black dot is present in cell J2.

I, GARY D. HAHN, in a field survey on MAY 3, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This corner not established during GLO survey.
1864 F. Stinson "Cen. sec. established by S.H. Truck and witnessed by myself as follows:
B. Walnut 3 N1°W 1.58 Maple 2 S27°W .88"
1888 E. Strong "Brick or found stake hole by Stinson or Found stone"
1893 E. Strong Co. Sur. "Found stone Elm 10 S45°W 52"
1899 E. Strong "Found drilled stone by Stinson"
1974 Gove Assoc. Inc. notes call for "T" iron.
Date? KCRC notes: Apple 8" S20°W 40 lks. Elm 10" S45°W 52 lks. BW 3" N1°W 158 lks.
(H) Sug 2" S27°W 158 lks. (W) S.E. cor. house NW 300.4' N. face fence post 27.7'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found bent "T" iron on its side.
Found 5" x 12" x 19" stone pointed up with brick on north side and surrounded by stones.
Found 18" x 20" flat stone beneath stone & brick (no drill hole). "T" iron was lying against stone point on west side of point.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
6-15-95



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L2, Center of Section 1, T2S, R12W, Ratified by Kalamazoo County Remonumentation Peer Group on June 15, 1995. This position not established by original government surveyors. This monument (pointed stone) is accepted as the best available evidence of the position of the corner. Removed "T" iron and stones and replaced with a 20" Harrison Monument in mon. box.

Fnd. 1" capped rebar (RLS 12023) South 32.93'
Fnd. nail with tab in 18" Oak (set P.K. nail over) South 33.78'
Fnd. nail with tab in 16" twin Maple S42°E 34.09'
Base of leaning R.R. tie fence post South 27.94'
Set nail in 13" Walnut North 28.09'
Set P.K. nail in 12" Maple N52°W 43.36'
Set P.K. nail in 13" Twin Maple S41°W 36.46'

Signed by [Signature] Date 8-31-95
Surveyor's Michigan License No. 38116