

APR 01 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

95 DEC 8 AM 10 55

For corners in
KALAMAZOO
(County)

Located In:

Corner Code #

OSHTEMO TWP.

1. Public Land Survey	T	2S	R	12W	L3
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

James Young
CLERK-REGISTER

LIBER 1 1400

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Gary D. Hahn, in a field survey on August 28, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1929 Quarter post established by U.S. Deputy Surveyor Geo. W. Harrison. Accessories: Beech 16 S79°E 321 Beech 6 N29°W 131

1977 Gove Assoc., Inc. T.J.W. 1/2" iron bar 6' south of centerline road in line with fence to south. 36" Beech South 25.62' 32" Maple North 36.18' 12" Maple N40°W 43.88'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original monument and accessories not recovered.

Found 1/2" dia. x 21" long rod in mon. box. Removed box and began digging around rod. Rod was surrounded by forty+/- 3"-7" dia. stones. Removed stones and rod and dug down to a point 24" below road sub base. Found a large pointed blue stone with a 1/4" dia. x 1/4" deep divot in the point. Divot had yellow lumber crayon markings in it. Stone was approximately 0.10' South of 1/2" dia. rod.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
9-21-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L3, North quarter corner section 12, T2S, R12W, Ratified by Kalamazoo County Remonumentation Peer Group on September 21, 1995. Location of pointed blue stone is accepted as a careful and faithful perpetuation of the position of the original corner. Set 20" Harrison monument over stone in a monument box.

- Set P.K. nail in 32" Beech South 25.48'
- Set P.K. nail in 33" Maple N37°W 43.52'
- Set P.K. nail in 6" Twin Maple N45°E 42.22'
- Metal Fence Gate Post S32°W 48.58'

Signed by

Gary D. Hahn

Date November 17, 1995

Surveyor's Michigan License No. 38116

