

**SURVEY &
REMONUMENTATION**

FEB 26 1998

7-
2-

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

LIBER 2PAGE 260

Oshtemo Township
For corners in Kalamazoo
(County)

Located In: Corner Code #

1. Public Land Survey	T	<u>2S.</u>	R	<u>12W.</u>	<u>L-11</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
.97 DEC 22 PM 3:49
Clerk - Registrar
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Allen H. McMachen, in a field survey on December 4, 1995
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current
manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and
5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a
Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found
as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1830 - George Harrison, D.S., Set quarter Section post, Burr Oak 12" N. 73° E. 2163 lks., Burr Oak 13" N. 40° W. 111 lks..
±1877 - F. Hodgman, C.S., "Bisected 1-2 set stake with stone over mound, Maple 2" N. 56½° E. 66 lks., DO. 4" S. 17° E.."
1880 - Ed Strong, C.S., Measured N¼-S¼ at 5288.58'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1¼" pipe in 5" steel sleeve, 5" below road grade. Removed pipe and found pointed stone 2.2' below grade. Stone is 0.05' South and 0.30' West of 1¼" pipe location and was surrounded by small stones and crockery. Measured East 2631.71' from found stone at South quarter corner to State of Michigan brass cap at the Southeast corner. Also found State of Michigan brass cap ±5.5' North and ±3.5' West of found pointed stone at South quarter corner. Measured South 5287.2' from found pointed stone at South quarter corner, Section 25 to South quarter corner, Section 36.

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
11-20-1997**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner

Found pointed stone is accepted as a careful and faithful perpetuation of the position of the original corner. Placed 20" Harrison Monument over point of stone and monument box over, Accessories:

- Nail & Tab in U. Pole N. 40° E. 48.18'
Nail & Tab in 28" Maple N. 55° W. 76.91'
Nail & Tab in U. Pole S. 45° W. 59.10'
N.W. corner concrete sign base-State of Michigan
Historical marker "Harris Family" S. 45° E. 46.85'



Signed by Allen H. McMachen
Surveyor's Michigan License No. 16935

Date 12/9/97