

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

'94 JAN 13 PM 4 04

For corners in OSHTEMO TWP.

KALAMAZOO  
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 2S R 12W L-12
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

LIBER

1 PG 1066

Register of Deeds Stamp & File Number

*James P. [Signature]*  
CLERK-REGISTER

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35				
13													

I, Allen H. McMachen a field survey on November 5, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1878 - Hodgeman bisected North line of Sec. 36, placed stake and stone in mound at North quarter corner. He found a stone and one witness at South quarter corner. He ran and bisected North and South quarter line setting a stone for the Center.

RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: 12-30-93

Bisected North line of Sec. 36 and set temporary point for North quarter (Temp. pt. fall 5.5 feet N. and 3.5 feet W. of existing survey marker at center line - center line. Found monument box at South quarter (placed by others from witnesses after sewer construction). Ran N. and S. quarter line and bisected it. Found an iron rod which was placed over a found pipe during W.D.I. Job #1786 in 1966. The iron was 0.78 East of the 0.74 North of bisection of quarter line. Dug 4'x 7'x 5' deep, found that the surface iron was inside of older, deeper pipe, also found pointed stone with drill hole pointing down beside pipe, found no further evidence of a corner in excavation.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found pipe is accepted as a careful and faithful perpetuation of the position of the original corner established by Hodgeman. Removed pipe and replaced with standard 30" Harrison Monument, accessories:

- 36" Oak N. 18 deg. W. 65.09'
- 24" Maple N. 55 deg. E. 33.07'
- 30" Maple S. 23 deg. E. 63.99'
- 24" Maple S. 62 deg. W. 61.21'

Signed by Allen H. McMachen  
Surveyor's Michigan License No. 16935

Date 1/13/94

