



LC-000039  
Page: 1 of 1  
10/28/1999 03:11P  
Bk-2 Pg-492

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Kalamazoo</u> (County)	Located In:	Corner Code#
Climax Twp.		
1. Public Land Survey	T <u>3S</u> R <u>9W</u>	<u>A12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

SURVEY & REMONUMENTATION

FEB 08 2000

SECTION

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Gary D. Hahn, in a field survey on August 5, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner not established by G.L.O. Survey.

1875 - F. Hodgman: "Set marked stone 44 lks. South of the East Quarter Post Section 36, Pavilion (stone by Nutting)."

KCRC Witness Ties:

(W) PL. Iron 6/18/40

(W) PL. 29.04 feet S. of East Quarter Post Section 36, Pavilion

RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
9-23-1999

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 1/2" x 1/2" diameter 10" long square bar in centerline of 36<sup>th</sup> Street and inside a 2" diameter 3" long pipe. Removed bar. Found a 1/2" diameter 18" long rod 2.4 feet below road surface slightly bent to the South. Removed. Excavated a 4' x 5' x 6' deep hole through mostly sandy soil. Found no stone. Rod was 0.06 feet North and 0.14 feet West of bar.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A12, West Quarter Post of Section 31, Town 3 South, Range 9 West. Ratified by the Kalamazoo County Remonumentation Peer Group on September 23, 1999. The position of the found bar is accepted as the best available evidence of the position of the original corner. Set a 20" Harrison Monument in a monument box in place of bar.

Witness Ties:

Found a Harrison Monument in a monument box North 29.01 feet (Pavilion corner M12)

Found PK nail in 48" Maple S 35° E 50.73 feet

Found PK nail in dead tree N 55° W 50.95 feet

Found PK nail in 18" Maple N 89° E 44.29 feet



Signed by [Signature]  
Surveyor's Michigan License No. 38116

Date 10/18/99

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975  
REVISED JAN., 1983 REVISED OCT., 1996