

APR 01 1996

COMMISSION

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

95 DEC 8 AM 10 55

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in KALAMAZOO Located in: _____ Corner Code # _____
(County)

CLIMAX TWP.

1. Public Land Survey	T <u>3</u> S <u>R</u> <u>9</u> W	<u>B3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

James J. Young
CLERK-REGISTER

LIBER 1 1387

Register of Deeds Stamp & File Number

I, GARY D. HAHN, in a field survey on MAY 2, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1826 Quarter post established by Deputy Surveyor Robert Clark, Jr. W. Oak 10 in S87°E 48½ lks. R. Oak 19 in S87°W 15½ lks.
- 1871 F. Hodgman Co. Sur. Fnd. stake from testimony of residents. Put stone around & witnessed. B. Walnut 10 in N40°E 1.79 B. Oak 8 in S40½°W 1.62
- 1883 F. Hodgman Fnd. stake & stones and witness of resurvey standing. Put in 3 ft. of earthen post at corner.
- 1977 Terry Woldring LCRC Liber 1, Page 687 RLS 22446 "Reset 5/8" iron rod on prorota from adjacent corner". set in mon. box 14' N. of centerline road. 20" Ash N14°E 16.58' 18" Pine N73°E 54.22' 12" Ash S47°E 49.11' 10" Ash S14°W 39.61'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original monument and accessories not recovered. Stone and earthen post not recovered.
Found 1/2" rebar (no mon. box) Removed rebar and dug a 4' x 8' x 3.5' deep hole into natural sand
Found nothing. Reset rebar in mon. box 15'+/- North of centerline road in road shoulder.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
6-15-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B3, South quarter corner Section 6, T3S, R9W, Ratified by Kalamazoo County Remonumentation Peer Group on June 15, 1995. Location of 1/2" rebar is accepted as a careful and faithful reestablishment of the position of the original corner. Removed rebar and replaced with a 30" Harrison Monument in mon. box.

- Fnd. nail with white tab in 26" Oak N14°E 16.57'
- Fnd. nail with white tab in 17" Pine N78°E 54.27'
- Fnd. cabin spike in 16" Oak S44°E 49.45'
- Fnd. cabin spike in 13" Oak S15°W 39.48'

Signed by *Gary D. Hahn*

Date 8-31-95

Surveyor's Michigan License No. 38116

