

SURVEY & REMONUMENTATION

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
'93 NOV 29 PM 2 21

For corners in

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
Climax Township	T <u>3 S</u> R <u>9 W</u>	<u>B-9</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

James J. Spang
CLERK-REGISTER

LIBER 1 PG 1034

Register of Deeds Stamp & File Number

I, John G. Kester, in a field survey on August 9, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9	●												
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
Corner Post established by U S Government Deputy Surveyor Robert Clark, 1826, Accessories: W Oak 8 N70E 42, W Oak 8 S53W 2 1/2'.
Remonumentation by F. Hodgeman, 1883, Found Stone of former Survey and side Stones 50 Lks North & South from it. Bored 3', put 1' Earthen Post at bottom then 1' broken Brick and 1' Earthen Post with Stone around at the top, just below surface.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Original Corner with accessories not recovered.
Found 1/2" Iron over broken Solid Clay Tile above Stone with Stone and Brick around 14" below surface. All were above 2nd Solid Clay Tile with X on top which was 37" below surface as called for in 1883 Remonumentation by F. Hodgeman.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
9-16-93

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
B-9, S 1/4 Corner Section 19, T3S-R9W, Ratified by Kalamazoo County Remonumentation Program Peer Group on September 16, 1993. Found 1/2" Iron over broken Solid Clay Tile above Stone with Stone and Brick around above 2nd Solid Clay Tile with X on top as called for by 1883 Remonumentation by F. Hodgeman and is accepted as a careful and faithful perpetuation of the Original Corners position. Removed 1/2" Iron, broken Tile, Stone with Stone & Brick around. Placed 30" Harrison Monument above lower Solid Clay Tile with X on top and placed Monument Box over Corner.

- Set P.K. Nail in 8" Mulberry North 39.47'
- Set P.K. Nail in 19" Cherry N50E 49.98'
- Set 1/2" Rebar S60W 36.88'
- Set 1/2" Rebar S60E 34.30'

Signed by *John G. Kester* Date 11-26-93

Surveyor's Michigan License No. 16046

Kalamazoo County Road Commission