

**SURVEY & REMONUMENTATION**

APR 27 1995

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
 COUNTY OF KALAMAZOO  
 RECEIVED FOR RECORD

'95 JAN 13 AM 11 50

For corners in

Kalamazoo  
 (County)

Located In:

Corner Code #

1. Public Land Survey	T 3 S R 9 W	C8
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous	S ___ T ___ R ___	_____
Property in Sec.	S ___ T ___ R ___	_____

*Janeit J...*  
 CLERK-REGISTER

LIBER 1 PG 1260

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Gary D. Hahn, in a field survey on June 6, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:  
 Quarter Section Post established by U.S. Deputy Surveyor Robert Clark, Jr. in 1826.  
 Accessories: Yellow Oak 16" S 40½°W 122 lks. White Oak 20" N 12½°E 87 lks.  
 1861 accessories by F. Stimson: W. Oak 16" N70½°E 160½ lks. W. Oak 17" N43°E 163½ lks.  
 1863 E. Strong "Stone unknown".  
 1883 F. Hodgeman "Found large boulder with drill hole for corner set by R. Nutting with side stones 50lks. each east & west."  
 1966 I.W.M. Inc. accessories: 5/8" drill hole in headwall S85°W 26.23' U. pole S70°W 64.47' 30" Oak S75°E 46.0' Found stone. 24" Apple East 43.0' 12" Twin Oak N60°E 44.46'  
 1976 Wilkins & Wheaton, Inc. Fnd. spike 4" down about centerline road. Accessories: 36" Apple East 43.4' 20" Double Oak N30°E 44.4'

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Original corner with accessories not recovered.  
 Found cabin spike 6" under asphalt patch in road.  
 Found 18" dia. boulder with 5/8" drill hole directly below said cabin spike 4.5' below asphalt.  
 Accessories from section A above still existing (new measurements):  
 5/8" drill hole in center of conc. headwall S85°W 26.33' (Headwall was later removed in 1994 reconstruction of 38th street).  
 Fnd. P.K. nail in 38" Apple east 43.51'  
 Fnd. P.K. in U. pole S70°W 64.49'

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
 12-15-94

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 C8, E¼ Corner Section 19, T.3S., R.9W.  
 Found 18" dia. boulder with 5/8" drill hole 4.5' below asphalt patch directly below fnd. cabin spike. Boulder is believed to be same as called for in 1883 notes by F. Hodgeman and is accepted as a careful and faithful perpetuation of the original corner position. Removed cabin spike and placed 30" Harrison monument centered over drill hole in boulder. Placed monument box over mon..  
 Accessories: P.K. nail in N. face 38" Apple East 43.51'  
 P.K. nail in U. pole S30°W 78.00'  
 P.K. nail in U. Pole S70°W 64.49'  
 P.K. nail in 39" Oak S34°E 45.80'

Signed by *Gary D. Hahn*

Date 11-4-94

Surveyor's Michigan License No. 38116

