

**SURVEY &
REMONUMENTATION**

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

'93 NOV 29 PM 2 21

For corners in

| | | |
|---------------------------------------|-------------------------|---------------|
| <u>Kalamazoo</u> (County) | Located In: | Corner Code # |
| Climax Township | | |
| 1. Public Land Survey | T 3 S R 9 W | C-9 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

James P. Young
CLERK-REGISTER

LIBER 1 PG 1035

Register of Deeds Stamp & File Number

I, John G. Kester, in a field survey on August 9, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Corner Post established by U S Government Deputy Surveyor Robert Clark, 1826,
Accessories: Beech 8 N64E 20, W Wood 30 N31W 12 1/2.
Remonumentation by F. Hodgeman, 1883, Found Large Boulder with Drill Hole set by R. Nutting for Corner, and side Stones South 50 Lks and N45W 71 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Original Corner and Accessories not recovered.
Found 1/2" Iron over Large Boulder with Drill Hole 13" below road surface as called for in 1883 Remonumentation by F. Hodgeman.

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
10-6-93**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
C-9, Corner of Sections 19, 20, 29 & 30, T3S-R9W, Ratified by Kalamazoo County Remonumentation Program Peer Group on October 6, 1993. Found 1/2" Iron over Large Boulder with Drill Hole as called for in 1883 Remonumentation by F. Hodgeman and is accepted as a careful and faithful perpetuation of the Original Corners position. Removed 1/2" Iron. Placed 12" long Solid Clay Tile encased in Cast Iron Sleeve with X on top above Large Boulder with Drill Hole. Placed Monument Box over Corner.

- Set P.K. Nail in Fence Post N50W 51.49'
- Set P.K. Nail in Fence Post N45E 52.10'
- Set P.K. Nail in 10" Box Elder South 32.36'
- Set P.K. Nail in 9" Box Elder S70W 82.61'

Signed by *John G. Kester* Date 11-26-93

Surveyor's Michigan License No. 16046

Kalamazoo County Road Commission