

MAY 28 1997

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **CLimax Twp.**

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>3S</u> R <u>9W</u>	<u>D-03</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

96 APR 15 PM 1 58

Register of Deeds Stamp & File Number

CLERK - REGISTER

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert E. Snell, in a field survey on Sept. 24 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3		☀										
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1826: United States Government Surveyors; set 1/4 Section post.  
W. Oak 22" S. 22° W. 50 lks.  
Y. Oak 20" N. 49° E. 11 lks.

1883: F. Hodgman, County Surveyor; corner destroyed grading road. Ran N. 22° E. 50 lks. from bottom of an old stump supposed to be of U.S. Bearing Tree. It came 50 lks. North of Board at the School Lot and exactly in line with fence North and South. Bored 3', filled one foot with stones and put 2' earthen post over with stones around just to surface of road.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1977: Allen McMachen, R.L.S. #16935; recorded survey L-1, P-960 and L.C.R.C. L-1, P-717, North 1/4 post Section 8, T. 3 S., R. 9 W., iron in monument box.

18" Oak North 35.70'  
15" Oak S. 15° W. 38.60'  
20" Oak S. 45° W. 64.84'

1996: Found 3" round tile, 2.5' below surface of road and under 1/2" x 18" rerod in monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-03: South 1/4 post Section 5, T. 3 S., R. 9 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on October 17, 1996 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile 2.5' below surface of road, as placed by F. Hodgman, County Surveyor in a remonumentation survey in 1883. Placed 20" Harrison Monument over tile in monument box.

PK Nail in West Side 29" Oak North 35.91'  
PK Nail in East Side 20" Oak S. 32° W. 38.81'  
PK Nail in East Side 27" Oak S. 68° W. 80.32'  
PK Nail in West Side 30" Walnut N. 28° W. 35.79'

Signed by Robert E. Snell  
Surveyor's Michigan License No. 9734

Date 11-14-96