

SURVEY & REMONUMENTATION

MAY 28 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER

2 PAGE 095

For corners in Climax Twp.

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 3S R 9W	D-05
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
1996 DEC 11 PM 2 51
Kalamazoo Register
CLERK-REGISTER
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on April 18, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5			17		16		15		14		13	
6	18											
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

1826: United States Government Surveyors; set 1/4 Section post.

Wh. Oak 10" N. 11° E. 58 lks.
Wh. Oak 8" S. 67° E. 50½ lks.

1883: F. Hodgman, County Surveyor; found large boulder with drill hole for corner 2' below surface of road and side stones 50 lks. each North and South, said to have been set by R. Nutting. Placed a 1 foot earthen post with stones around over drill hole in boulder.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1884: Wilkins & Wheaton Engineering Co., found tile.

Fence Post South 32.8'
South Edge of Pavement 8.4'

1996: Found 1/2" x 18" long iron bar over tile with cross in top.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
11-21-1996

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-05: South 1/4 post Section 8, T. 3 S., R. 9 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on November 25, 1996 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile as set by F. Hodgman, County Surveyor in 1883 remonumentation survey. Placed remonumentation sleeve over tile in monument box.

PK Nail over Existing Nail on North Side of 8" Twin Hickory S. 54° E. 48.26'
PK Nail over Existing Nail on East Side of 14" Oak South 37.25'
PK Nail over Existing Nail on West Side of 18" Oak S. 20° W. 26.27'
PK Nail on North Side of 15" Oak S. 74° W. 89.17'

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date 12-10-96