

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

NOV 18 AM 10 51

For corners in

Kalamazoo <small>(County)</small>	Located In:	Corner Code #	
Climax Township			
1. Public Land Survey	T <u>3S</u> R <u>9W</u>	<u>D-9</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

[Signature]

CLERK-REGISTER

LBER 1 PG 1177

Register of Deeds Stamp & File Number

I, John G. Kester, in a field survey on August 9, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		13		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner Post established by U S Government Deputy Surveyor Robert Clark, 1826, Accessories: Beech 9 S10W 12, D O 20 N84W 26½. Remonumentation by F. Hodgman, 1883, Found Large Boulder with Drill Hole for Corner set by Nutting and side Stone 50 lks North. Kalamazoo County Road Commission Notes of 1919 do not state what was found for corner but show witnesses as: Butternut 10" N30W 37.0, Elm 16" SW 52.0, Fence N on line.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original Corner and Accessories not recovered. Large Boulder with Drill Hole set by Nutting and confirmed by Hodgman in 1883 along with side Stone not recovered. Found ½" Iron Rod above and 0.10' West of ½" Pipe with small stones around. No additional evidence was found in the 20'x25'x4.5' deep excavation. It appears that all other evidence was removed during road reconstruction.

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP**
10/6/93 *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-9, S¼ Corner Section 20, T3S-R9W, Ratified by Kalamazoo County Remonumentation Program Peer Group on October 6, 1993. Found ½" Iron Rod - Found ½" Pipe with small stones around and is accepted as the best available evidence of the position of the Original Corner. Removed ½" Iron Rod. Replaced ½" Pipe, with small stones around, with a 30" Harrison Monument and placed Monument Box over Corner.

- Set P.K. Nail in P.P. N3°27'E 37.96'
- Set P.K. Nail in 48" Maple S25°44'W 73.38'
- Set P.K. Nail in 26" Maple S60°54'W 66.02'
- Set P.K. Nail in 23" Hickory S66°29'W 77.26'

Signed by *[Signature]* Date November 15, 1994

Surveyor's Michigan License No. 16046
Kalamazoo County Road Commission