

SURVEY & REMONUMENTATION

FEB 26 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
97 DEC 29 AM 10 56
Clerk - Register
Annelle Johnson

7-
2- SECTION
For corners in Climax Twp.

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T3S R9W	D-11
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

LIBER 2 PAGE 279

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on Sept. 29, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1826: United States Government Surveyors; Set 1/4 Section post.

Lynn 14" N. 25° E. 38 lks.
Lynn 14" S. 56° E. 38 lks.

1883: F. Hodgman, County Surveyor; "Found stone of former survey with old stake under it at angle of roads. Put 1 ft. earthen post 3 feet deep, than 1 foot of small stones and 1 foot earthen post on top with stones around. Set side stone 50 lks. East".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1937: Wilkins & Wheaton Engr. Co.; found tile in road.

1953: Wilkins & Wheaton Engr. Co.; found tile and placed iron over tile.

1997: Found long nail over bent iron 6" below bituminous surface, at 18" below surface found 3" round clay tile with "x" on top. Noted nail was 0.05' West and 0.15' South of tile, also center line of 39th Street, West 2.0'.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-11: South 1/4 post, Section 29, T. 3 S., R. 9 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on December 18, 1997 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile as placed in 1883 Remonumentation Survey by F. Hodgman, County Surveyor. Placed 16" or 20" Harrison Monument over tile in monument box.

Existing Nail in North Side	Power Pole	S. 80° E.	29.85'
PK Nail in North Side	"Maple Clump"	S. 56° E.	55.85'
Existing Nail in West Side	Power Pole	S. 46° W.	85.95'
Center Line	Drain to East	South	40.00'

Signed by *Robert E. Snell*
Surveyor's Michigan License No. 9734

Date 12-23-97