

**SURVEY &
REMONUMENTATION**

JUL 23 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Climax Twp.

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>3S</u> R <u>9W</u>	<u>E-03</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
196 DEC 31 AM 8 52
LIBER 2PAGE 100
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on Oct. 7, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP 12/19/1996**

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3				●								
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

1826: United States Government Surveyors; set post, corner to Sections 4, 5, 8 & 9.
Y. Oak 22" S. 87° E. 171 lks.
Wh. Oak 36" N. 01° E. 149 lks.

1883: F. Hodgman, County Surveyor; "found stake of resurvey set by me in 1868 from one U.S. Bearing Tree then standing N. 01° E. 140 lks. distant, on removing this stake and boring down, I found at a depth of 3' a part of an older stake still sound in wet earth, left old stake in place, placed 1' of small stones and 2' earthen post over and noted Maple 3" S. 45½° E. 108 lks. distant, Wh. Oak 8" S. 01° E. 175 lks. distant."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996: After digging several large holes found an old culvert headwall where the position of the corner should be. Ran a straight line from Southwest corner Section 4 (G-03) thru South 1/4 post of Section 4 (F-03) and equidistance apart and set ½" x 18" rered at Southwest corner Section 4 (E-03). This procedure is how F. Hodgman set the "lost" corner at the South 1/4 post (F-03) in 1883. The distance from South 1/4 post to Southeast corner equals 2,631.20 feet and from South 1/4 post to Southwest corner 2,631.20 feet compared to 2,635.38 feet as measured by F. Hodgman in 1883.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-03: Southwest corner of Section 4, T. 3 S., R. 9 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on December 19, 1996 and is accepted as a careful and faithful re-establishment of the position of the original corner. Placed 20" Harrison Monument in place of 1/2" x 18" rered in monument box.

PK Nail in Top	Wood Fence Post	S. 06° W.	52.94'
"X" in Top	N. end 18" Culvert (Conc.)	N. 60° W.	34.24'
Hole in Top	4½" Concrete Post	N. 10° W.	11.51'
½" x 18" Iron	in center line "0" Ave.	S. 08° W.	20.92'

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date 12-30-96