

SURVEY & REMONUMENTATION

FEB 26 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
97 DEC 17 AM 9 30
CLERK - REGISTER
LIBER 2PAGE 244
Register of Deeds Stamp & File Number

7- SECTION
2- For corners in Climax Township

| Kalamazoo (County) | Located In: | Corner Code # |
|------------------------------------|-------------|---------------|
| 1. Public Land Survey | T 3S R 9W | E-13 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on August 18 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

1825: United States Government Surveyors; Set Post, Corner to Sections 2 & 3.
Elm 14" N. 78° W. 91lks.
Beech N. 67° E. 36lks.

1883: F. Hodgman, County Surveyor; "3 (S.E. Corner Section 32) Found stake hole by measuring from one U.S. Bearing Tree and from corner post of Sections 4 & 5, Wakeshma, standing. Set 3 ft. earthen post, 3" below surface and marked Beech 6" diameter North 3 lks. Corner Sections 4 & 5 East 49 lks., set 1 ft. earthen post."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995: Found 3" round tile in South bank of Hendrixson Drain, down about 18". Top of tile was found in the bottom of the ditch (a "mushroom" top). Tile as found had "X" in top. 32.28' West of tile corner Sections 4 & 5. Drain to North, West 13'.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
9-18-1997

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13: Southeast corner, Section 32, T. 3 S., R. 9 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on September 18, 1997 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile with "X" on top 18" below surface. Tile was set by F. Hodgman, County Surveyor in 1883 Remonumentation Survey. Placed Remonumentation Sleeve over tile.

| | | | |
|-------------------------|------------|-----------|--------|
| P.K. nail in West Side | 12" Oak | S. 50° E. | 32.90' |
| P.K. nail in West Side | 9" Maple | S. 10° E. | 29.90' |
| P.K. nail in West Side | 18" Poplar | S. 22° W. | 31.55' |
| P.K. nail in South Side | W. Cherry | S. 88° W. | 4.72 |

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date Nov. 25-1997