

**SURVEY &
REMONUMENTATION**

7- JUL 23 1997
2- COMMISSION

LIBER 2 PAGE 117

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Climax Township Located In: _____ Corner Code # _____
Kalamazoo (County)

1. Public Land Survey	T	<u>3S.</u>	R	<u>9W.</u>	F-1
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Section	S	_____	T	_____	R
	S	_____	T	_____	R

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
.97 MAR 20 PM 3 35
CLERK - REGISTER
[Signature]
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

I, Allen H. McMachen, in a field survey on January 24, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner not set by Government Surveyors
1825 - John Mullett, D.S., N.W. corner, Sec. 4 (E-1)
"Intersected North boundary 112 lks. East of post" Wh. Oak 14" S. 83 1/2° E. 451 lks.
N.E. corner, Sec. 4
"Intersected North boundary 139 lks. East of post"
Calculated jog at N 1/4 cor. = 82.83'

1874 - F. Hodgman, C.S., N.W. cor., Sec. 4
"Set a temporary stake from one living witness S.E. as things do not agree well around here and parties are not willing to spend the necessary time to settle the matter. I only set a temporary stake". (Accompanying map shows the Northwest cor. of Sec. 4 at 2.02 chains East of Charleston cor.)

1883 - F. Hodgman, C.S., N.W. cor., Sec. 4.
"Ran N. 83 1/2° W. 451 lks. from stump of W. Oak 14 U.S. bearing tree with one plain and set 3' earthen post in the marsh. No convenient witness trees near. This post is very nearly in line with the quarter post and Section corner South but is 204 1/2 lks. instead of 139 lks. East of corner of Sections 32 and 33 in Charleston.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found clay tile 105.09' East of clay tile at S 1/4 cor., Sec. 33, Charleston Twp. Clay tile at N 1/4 cor. is 2.65' West of fence to South and is 0.8' above grade. Using Hodgman's 1883 jog at N.W. corner (204 1/2 lks.) and the original government jog (112 lks.) at the N.E. corner the calculated jog at the N. 1/4 corner should be 316 1/2 lks. (104.44')

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
2-27-1997**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found clay tile is the best available evidence of the position of the corner. Reset tile to 0.15' above grade and placed standard sleeve over tile, Accessories:

- Nail in North side 26" Cherry N. 86° E. 218.64'
- Nail in South side 28" Twin Cherry N. 89° E. 182.00'
- 8" Dia. fence corner post East 2.65'
- S. 1/4 cor., Sec. 33, Charleston Twp. West 105.09'



Signed by Allen H. McMachen
Surveyor's Michigan License No. 16935

Date 3/18/97