

**SURVEY &
REMONUMENTATION**

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

93 NOV 29 PM 2 21

For corners in

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
Climax Township		
1. Public Land Survey	T <u>3</u> S <u>R</u> 9 W	<u>F-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

James P. Young
CLERK-REGISTER

LIBER 1 PG 1037

Register of Deeds Stamp & File Number

I, John G. Kester, in a field survey on August 10, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 Corner Post established by U S Government Deputy Surveyor Robert Clark, 1826,
 Accessories: Beech 14 S40W 40, Beech 30 N71E 10.
 Survey by Ed Strong, 1872, Found Stake from Stump of one witness. Set Stone with Drill Hole, Accessories: Side Stone North 50 Lks, Whitewood 36 S19E 120½ Lks.
 Remonumentation by F. Hodgeman. 1883, Found old Stake with Stone over it, side Stone 50 Lks South and Stump of Whitewood bearing tree S19E 120½ Lks. Bored 3' filled bottom 2' with broken Brick and small Stones. Put 1' Earthen Post over with Stone around and covered with flat Stone over all.
 LCRC by M. E. DeKeyser, 1974, shows existing ½" Iron, Accessories: U Pole N30E 43.65', 14" Maple N20W 35.7', 2.5' South c/l pavement, St Sign S60E 38.6'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Original Corner and Accessories not recovered.
 Found ½" Iron over ½" PIPE believed to be same as recorded in 1974 LCRC by DeKeyser.
 Found Solid Clay Tile with X on top over Stones & Brick (40" below road surface and 3.13' West & 0.15' South of ½" Pipe) as called for in 1883 Remonumentation by F. Hodgeman.

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
9-16-93**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 F-9, S¼ Corner Section 21; T3S- R9W, Ratified by Kalamazoo County Remonumentation Program Peer Group on September 16, 1993. Found ½" Iron over ½" Pipe is incorrect. Found Solid Clay Tile with X on top over Stones & Brick as called for in 1883 Remonumentation and is accepted as a careful and faithful perpetuation of the Original Corners position. Removed ½" Iron & ½" Pipe. Placed 30" Harrison Monument above Solid Clay Tile, with X on top, over Stones & Brick and placed Monument Box over Corner.

- Set P.K. Nail in 22" Maple N15W 31.50'
- Set ½" Rebar N15E 36.36'
- Set P.K. Nail in 18" Apple S45E 62.58'
- Set P.K. Nail in 6" Maple S50W 62.75'

Signed by John G. Kester Date 11-26-93

Surveyor's Michigan License No. 16046
 Kalamazoo County Road Commission