

MAY 16 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

'96 MAR 13 PM 3 43

For corners in Kalamazoo (County) Located In: Climax Twp. Corner Code #

- 1. Public Land Survey T 3 S. R 9 W. G-01
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R

James J. Young
CLERK-REGISTER

LIBER 1 1455

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13. A small circle is drawn around the intersection of column F and row 2.

I, Robert E. Snell, in a field survey on January 22, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1826: United States Government Surveyors; intersected North boundary 112 lks. East of post. Set post at intersection corner to Sections 3 and 4.
Y. Oak 13" S. 60° E. 101 lks.
Y. Oak 15" S. 77° W. 37 lks.

1883: F. Hodgman, County Surveyor; found corner post of resurvey by S.C. Hodgman, set 3' earthen post in its place, 112 lks. East of corner of Section 33 & 34, Charleston.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1937: Wilkins & Wheaton Engr. Co.; found tile 75.74' East of tile for Southeast corner Section 33, T. 2 S., R. 9 W.
1996: Found 3" round tile with "x" on top as set by F. Hodgman, County Surveyor in a Remonumentation survey in 1883.

RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP 2-15-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-01: Northwest corner Section 3, T. 2 S., R. 9 W., Ratified by Kalamazoo County Remonumentation Program Peer Group on February 15, 1996 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile with "x" on top as set by F. Hodgman, County Surveyor in a remonumentation survey in 1883. Placed a remonumentation sleeve over tile.

Center line of Road (42nd St.) West 42.5'+
Southeast corner Section 33, T. 2 S., R. 9 W. (G-13) West 75.74'
PK Nail in South Side 46" Oak S. 64° E. 10.97'
PK Nail in East Side Cedar S. 08° W. 38.58'
PK Nail in North Side W. Cherry S. 32° W. 41.38'
Center line chain link fence post N. 88° W. 9.48'

Signed by Robert E. Snell Date 3-12-96

Surveyor's Michigan License No. 9734