

**SURVEY &  
REMONUMENTATION**

FEB 18 1994

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

'93 NOV 29 PM 2 21

For corners in

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
Climax Township		
1. Public Land Survey	T <u>3</u> S R <u>9</u> W	<u>G-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*James J. [Signature]*  
CLERK-REGISTER

LIBER 1 PG 1038

Register of Deeds Stamp & File Number

I, John G. Kester, in a field survey on August 10, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
Corner Post established by U S Government Deputy Surveyor Robert Clark, 1826, Accessories: Elm 18 S53E 22, B Ash 13 N34W 22½.  
Survey by Ed Strong, 1872, Found Stake, set square Stone with Drill Hole, Accessories: Side Stone North 50 Lks, B Ash 20 N71½E 110½ Lks, Maple 12 S40 3/4E 93 Lks. Remonumentation by F. Hodgeman, 1883, Found Stone of resurvey and remains of old Stake under it. Stumps of U S witness trees and of resurvey are standing, also side Stone 50 Lks South. Bored 3', filled 2' with broken Brick and Stones, 1' Earthen Post over and Stone around it. Accessories: W Ash 8 N43½W 90½ Lks, Elm 6 N2½E 78 2/3 Lks. LCRC by M. E. DeKeyser, 1973, Found existing Iron, Accessories: R.R. Rail Fen Cor S 31.0', U Pole N45W 66.92', 12" Maple Clump N15E 72.40'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Original Corner and Accessories not recovered.  
Found ½" Iron in Monument Box believed to be same as recorded in 1973 LCRC by M. E. DeKeyser.  
Found ½" Pipe 3.75' South and 0.67' East of ½" Iron in Monument Box.  
Found Solid Clay Tile with X on top, 3.62' South & 1.13' East of ½" Iron in Monument Box and 36" below road surface, with large Stone on West side and small Stones & Brick under Tile as called for by 1883 Remonumentation by F. Hodgeman.

**RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP**  
9-16-93

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
G-9, Corner of Sections 21, 22, 27 & 28, T3S-R9W, Ratified by Kalamazoo County Remonumentation Program Peer Group on September 16, 1993. Found ½" Iron in Monument Box and ½" Pipe are incorrect. Found Solid Clay Tile with X on top over Brick & Stones by 1883 Remonumentation and is accepted as a careful and faithful perpetuation of the Original Corners position. Removed ½" Iron, Monument Box and ½" Pipe. Placed 20" Harrison Monument above Solid Clay Tile with X on top and placed Monument Box over Corner.

Set P.K. Nail in 9" Cottonwood S45E 30.17'  
Center/Top R.R. Rail Fence Post South 27.25'  
Set P.K. Nail in P.P. N45W 47.40'  
Set P.K. Nail in 11" Ash North 47.16'

Signed by [Signature] Date 11-26-93

Surveyor's Michigan License No. 16046  
Kalamazoo County Road Commission