

**SURVEY & REMONUMENTATION**

AUG 06 1996

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Kalamazoo</u>	Located In:	Corner Code #
Climax <sup>(County)</sup> Twp.		
1. Public Land Survey	T <u>3S</u> R <u>9W</u>	<u>H-01</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
1996 JUN 7 PM 2 26  
Clerk-Register  
*Jessica Springs*  
LIBER 2 PAGE 021  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert E. Snell, in a field survey on Jan. 24, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1825: United States Government Surveyors; did not set this corner.
- 1883: F. Hodgman, County Surveyor; did not remonument this corner in the remonumentation survey of Climax Township in 1883.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1938: (June) Wilkins & Wheaton Engineering Co.; found iron 57.00' East of South 1/4 post (tile) of Section 34, Charleston Township.
- 1996: Found 1" iron bar 57.00' East of tile as noted above. Tile now has remonumentation sleeve over it.

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
5-2-1996  
*R.E.S.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-01: North 1/4 post Section 3, T. 3 S., R. 9 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on May 2, 1996. This position not established by original Government Surveyors. This monument is accepted as the best available evidence of the position of the corner. Found iron bar as noted in a survey by Wilkins & Wheaton Engineering Co. in June of 1938. Placed 30" Harrison monument in place of iron bar.  
Remonumentation sleeve over tile at South 1/4 Post of Section 34, T.2S.,R.9W.-West 57.00'

PK Nail on North Side of 10" Mulberry	S. 76° W.	35.95'
PK Nail on North Side of 14" Cherry	S. 32° W.	6.18'
PK Nail on East Side of 6" Cherry	S. 08° E.	17.85'
PK Nail on East Side of 5" Hickory	S. 06° W.	14.71'

Signed by *Robert E. Snell*  
Surveyor's Michigan License No. 9734

Date 6-6-96