

SURVEY & REMONUMENTATION

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

93 NOV 29 PM 2 21

For corners in

Kalamazoo (County)	Located In:	Corner Code -#
Climax Township		
1. Public Land Survey	T 3 S R 9 W	H-9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

James J. Gump
CLERK-REGISTER

LIBER 1 PG 1039

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, John G. Kester, in a field survey on August 10, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 Corner Post established by U S Government Deputy Surveyor Robert Clark, 1826,
 Accessories: Beech 11 N35W 25½, Beech 18 S24E 14.
 Survey by Ed Strong, 1871, Large Stone with +, Accessories: Beech 10 S8½E 54½ Lks,
 Beech 11 S63½E 72½ Lks, Walnut 8 N43E 134 Lks.
 Remonumentation by F. Hodgeman, 1883, Found Corner Stone and witness trees of
 resurvey all standing correct. Bored 3', put 1½' Broken Brick in bottom and 2'
 Earthen Post over with Stone around.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Original Corner and Accessories not recovered.
 Found ½" Iron in Monument Box over 10 pieces of Brick 32" below road surface.
 Extensive excavation revealed no other evidence of Corner position. It is believed
 that the Brick is the remains of the 1883 Remonumentation by F. Hodgeman and all
 other evidence was removed by previous road excavation in this area.

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
10-6-93**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 H-9, S¼ Corner Section 22, T3S-R9W, Ratified by Kalamazoo County Remonumentation
 Program Peer Group on October 6, 1993. Found ½" Iron in Monument Box over Pieces of
 Brick and is accepted as a careful and faithful perpetuation of the Original
 Corners position. Removed ½" Iron and Monument Box. Placed 20" Harrison Monument
 above pieces of Brick and placed Monument Box over Corner.

- Set P.K. Nail in 21" Box Elder North 58.25'
- Set P.K. Nail in 11" Cottonwood S45E 40.53'
- Set P.K. Nail in 10" Cottonwood S10E 30.30'
- Set P.K. Nail in 6" Box Elder S30W 38.34'

Signed by *John G. Kester* Date 11-29-93

Surveyor's Michigan License No. 16046
 Kalamazoo County Road Commission