

SURVEY & REMONUMENTATION

1 OCT 06 1997
2 COMMISSION

LIBER 2 PAGE 157

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Climax Twp.

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 3S R 9W	H-11
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
1997 JUL 29 AM 11 00
Janet J. Johnson
CLERK - REGISTER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on June 30, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11							●					
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

1825: United States Government Surveyors; set 1/4 Section post.

- Sugar 11" N. 32° W. 10 1/2 lks.
Sugar 14" S. 14° E. 21 lks.

1883: F. Hodgman, County Surveyor; "Found large boulder with hole drilled in it for corner, by R. Nutting."

Hickory 5" S. 39° W. 53 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997: Found large boulder with hole drilled in it (1/2" x 1/2") 0.65' below surface of bituminous road. Found Hickory tree (40") S. 39° W. 53 lks. (34.98') from 1883 (5").

R. E. Snell
RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP
7-16-1997

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-11: South 1/4 post, Section 27, T. 3 S., R. 9 W.; ratified by the Kalamazoo County Remonumentation Program Peer Group on July 16, 1997 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found large boulder set by R. Nutting, Surveyor and found and accepted in 1883 Remonumentation Survey by F. Hodgman, County Surveyor. Placed 5" of 10" Harrison Monument in concrete over drill hole in stone and placed 1 1/2" Paving Riser with cap over monument.

PK Nail in West Side	18" Maple	N. 08° W.	29.12'
PK Nail in West Side	40" Hickory	S. 39° W.	35.40'
PK Nail in East Side	6" Hickory	S. 06° E.	32.44'
PK Nail in Southeast Side	18" Hickory	N. 62° E.	46.36'

Signed by *Robert E. Snell*
Surveyor's Michigan License No. 9734

Date 7-28-97