

SURVEY & REMONUMENTATION

FEB 26 1998

7-
2-

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Climax Township

<u>Kalamazoo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>3S</u> R <u>9W</u>	H-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

97 DEC 17 PM 9 30

James J. Johnson
CLERK - REGISTER

LIBER **2** PAGE **245**
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on August 19, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1825: United States Government Surveyors: Set 1/4 Section post. Maple 4" N. 83 1/2° E. 42 lks., Black Ash 5" N. 54° W. 24 lks.
- 1871: F. Hodgman, County Surveyor: "Set stake from 2 living witness".
- 1883: F. Hodgman, County Surveyor: "Found stake at correct course and distance from one U.S. Bearing Tree and stump of other. Put in 3 ft. of earthen post.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1997: Found tile, top section broken and laying on its side. Second below it along side rotted of fence post. A second rotted of fence post is 2' East and 1' South. Approximately 242.2' West of drain.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
9-18-1997

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13: South 1/4 post, Section 34, T. 3 S., R. 9 W., ratified by Kalamazoo County Remonumentation Program Peer Group on September 18, 1997 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found tile North of East and West fence. Top section laying on its side and broken. Second section along very old fence post rotted off. Tile was set in 1883 Remonumentation survey by F. Hodgman, County Surveyor. Placed Remonumentation sleeve over tile.

Centerline Railroad Rail	Fence Corner	S. 80° E.	17.66'
P.K. nail in West side	16" Ash	S. 12° W.	14.45'
P.K. nail in West side	6" Ash	S. 66° W.	20.42'
P.K. nail in North side	18" Ash	S. 88° W.	19.38'

Signed by _____ Date 12-16-97
Surveyor's Michigan License No. 9734

Robert E. Snell