

**SURVEY & REMONUMENTATION**

1  
2  
AUG 06 1996

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Kalamazoo  
(County)  
Climax Twp.

Located In:

Corner Code #

- |                                      |               |               |             |
|--------------------------------------|---------------|---------------|-------------|
| 1. Public Land Survey                | T <u>3 S.</u> | R <u>9 W.</u> | <u>I-01</u> |
|                                      | T _____       | R _____       | _____       |
|                                      | T _____       | R _____       | _____       |
|                                      | T _____       | R _____       | _____       |
| 2. Property Controlling in Section   | S _____       | T _____       | R _____     |
|                                      | S _____       | T _____       | R _____     |
| 3. Miscellaneous Property in Section | S _____       | T _____       | R _____     |
|                                      | S _____       | T _____       | R _____     |

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
96 MAR 23 PM 1 47  
CLERK - REGISTER  
LIBER 1 PAGE 1492  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert E. Snell, in a field survey on March 18, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

1826: United States Government Surveyors; intersected North boundary, set post at intersection between Section 2 and 3.

Br. Oak 30" S. 40° E. 162 lks.  
Br. Oak 12" S. 14½° W. 117 lks.

1882: F. Hodgman, County Surveyor; corner lost, restored by prolonging the line over the Southwest corner and the West 1/4 post of the Section to intersect with town line 33 3/4 links East of the corner of Sections 34 & 35, Charleston Twp. Set 3' of earthen post. Burr Oak 16" S. 32½° E. 57½ lks., Burr Oak 16" S. 88° W. 52 lks.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1947: Wilkins & Wheaton Engr. Co.; found tile 12" deep top broken.

24" Oak	S. 88° W.	33.86'	North & South fence East 19.11' North & South fence West 44.23' in East and West fence line.
Centerline travelled road	West	12.0'	
20" Hickory	S. 20° E.	72.7'	

1996: Found 3/4" x 10" iron over tile 20" deep. Top Section of tile broken.

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
4-18-1996 *R.E.S.*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I-01: North Section corner common to Sections 2 & 3, T. 3 S., R. 9 W.; Ratified by the Kalamazoo County Remonumentation Program Peer Group on April 18, 1996 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile (top broken) as set by F. Hodgman, County Surveyor in a remonumentation survey in 1882. Placed 16" of 20" Harrison Monument over tile in monument box.

PK Nail on West Side of 22" Maple	N. 30° E.	76.38'
PK Nail on South Side of 10" Maple	N. 86° E.	23.66'
PK Nail on West Side of 7" Hickory	S. 12° E.	53.79'
Nail & Tab on South Side R.R. Tie Fence Corner	N. 80° W.	44.83'
Centerline of Road	West	12.3'

Signed by Robert E. Snell  
Surveyor's Michigan License No. 9734

Date 5-23-96