

**SURVEY &  
REMONUMENTATION**

FEB 18 1994

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

'93 NOV 29 PM 2 22

For corners in **COMMISSION**

<u>Kalamazoo</u> <small>(County)</small>	Located In:	Corner Code #
Climax Township		
1. Public Land Survey	T <u>3</u> S R <u>9</u> W	<u>I-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*James J. [Signature]*  
CLERK-REGISTER

LIBER 1 PG 1040

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, John G. Kester, in a field survey on August 10, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
Corner Post established by U S Government Deputy Surveyor Robert Clark, 1826,  
Accessories: Elm 8 N66W 64, Maple 9 N68E 73.  
Remonumentation by F. Hodgeman, 1883, Found Stake standing and witness trees of resurvey alive and good. Put down 3' Earthen Post and remeasured witness trees.  
Accessories: Elm 8 N57W 23 Lks, Elm 6" N31½E 59 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Original Corner and Accessories not recovered.  
Found ½" Iron - Found Solid Clay Tile with X on top, 0.37' South and 1.28' West of ½" Iron and 50" below road surface, as called for in 1883 Remonumentation by F. Hodgeman.

**RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP**  
9-16-93

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
I-9, Corner of Sections 22, 23, 26 & 27, T3S-R9W, Ratified by Kalamazoo County Remonumentation Program Peer Group on September 16, 1993. Found Solid Clay Tile with X on top and is accepted as a careful and faithful perpetuation of the Original Corners position. Removed ½" Iron. Placed 30" Harrison Monument above Solid Clay Tile with X on top and placed Monument Box over Corner.  
Set P.K. Nail in 6" Fence Post N9W 32.73'  
Set P.K. Nail in 6" Fence Post N55W 54.22'  
Set P.K. Nail in 35" Poplar S20E 47.25'  
Set 16 Penny Spike in 8" Fence Post S60E 60.96'

Signed by [Signature] Date 11-29-93

Surveyor's Michigan License No. 16046  
Kalamazoo County Road Commission