

FEB 08 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in CLIMAX TWP
KALAMAZOO
 (County)

Located In: _____ Corner Code # _____

| | | | | | |
|--------------------------------------|---|-----|---|-----|------|
| 1. Public Land Survey | T | 3S. | R | 9W. | J-10 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Section | S | | T | R | |
| | S | | T | R | |

PAGE 429
 RECEIVED FOR RECORD
 STATE OF MICHIGAN
 COUNTY OF KALAMAZOO

98 DEC 23 AM 3 53

LIBER
 CLERK - REGISTER

Handwritten Signature

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
6. IWM Job No. 30479

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

I, Allen H. McMachen, in a field survey on February 25, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner not placed by original government surveyors.
 1871 - S. Hodgman, "Stake by Nutting & found in line North and South & accepted as correct" (Hodgman's survey was in the Northeast quarter of Section 26 and made no reference to the West quarter corner).

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP

12/17/98
R. L. 8

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No corner marker was found. Placed Harrison Monument on the bisection of the North and South quarter line. Measured North 2650.68 feet to Harrison Monument at North quarter corner and measured South 2650.68 feet to drilled stone at South quarter corner. Corner placed on line between said North quarter corner and South quarter corner. Existing fence corner near the North eighth corner of the Southeast quarter is 1.5 feet South of a line extending from monument placed at Center quarter corner to standard marker at East quarter corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

This position not established by original government surveyors. Harrison Monument placed is accepted as the best available evidence of the position of the corner, Accessories:

- Nail & Tab on East side 32" Maple N. 12° W. 143.30'
- Nail & Tab on South side 14" Triple Walnut N. 26° E. 45.11'
- Nail & Tab on South side 10" Elm N. 89° E. 34.38'
- Nail & Tab on N.E. side 10" Maple S. 27° E. 91.04'



Signed by *Allen H. McMachen*
 Surveyor's Michigan License No. 16935

Date 12/23/98