

OCT 06 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Climax Twp.

LIBER 2 PAGE 159
 97 JUL 29 AM 11 00
 STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 J. Smith
 CLERK - REGISTER

Kalamazoo (County)	Located In:	Corner Code #
1. Public Land Survey	T 3S R 9W	K-01
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Robert E. Snell, in a field survey on May 20, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1826: United States Government Surveyors; Intersected North boundary 9 lks. (5.94') East of post. Set post at intersection, corner to 1 & 2.
 - Wh. Oak 14" S. 74½° W. 129 lks.
 - Y. Oak 16" S. 07½° E. 177 lks.
- 1883: F. Hodgman, County Surveyor; "Found no stake ran N. 74½° E. 129 lks. from Wh. Oak witness tree and set post 9 lks. (5.94') East of Charleston corner. Bored 3 ft., filled bottom with stone and put 2 ft. earthen post over."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1997: Found 3" round tile in North side of concrete base of 6" steel fence corner, 5.73' East of Charleston corner (K-13).

R. G. S.
RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP
 6-19-1997

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-01: Northwest corner, Section 1, T. 3 S., R. 9 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on June 19, 1997 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile placed in 1883 Remonumentation Survey by F. Hodgman, County Surveyor, in North Side of concrete base for 6" steel fence post. Tile in concrete fence post base to be retained as monument.

Exist. Nail/Tab in South Side	8" Oak	N. 56° E.	15.27'
Exist. Nail/Tab in East Side	12" W. Cherry	N. 30° E.	27.78'
Exist. Nail/Tab in East Side	22" Oak	N. 68° W.	15.96'
PK Nail in South Side	8" W. Cherry	N. 68° E.	14.79'
PK Nail in North Side	12" W. Cherry	S. 60° E.	23.40'

Signed by Robert E. Snell Date 7-29-97
 Surveyor's Michigan License No. 9734