

SURVEY & REMONUMENTATION

SEP 14 1998

SECTION 1

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER
CLERK - REGISTER

2 PAGE 311
198 SEP 3 PM 3 25
RECEIVED FOR RECORD

STATE OF MICHIGAN
COUNTY OF KALAMAZOO

For corners in Climax Twp.

Kalamazoo (County)	Located In:	Corner Code #
1. Public Land Survey	T 3S R 9W	K-05
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on May 14, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1826: United States Government Surveyors; set post corner to Section 11, 12, 13 & 14.

Beech 11" N. 02° E. 26 lks.
Black Ash 24" South 28 lks.

1876: F. Hodgman, County Surveyor; "Found stake from one witness. Set new stake Hickory 8" S. 25° W. 11½ lks.

1883: F. Hodgman, County Surveyor; "Replaced stake with 3 ft. earthen post and noted new bearing trees." Elm 12" N. 82° W. 39 lks., Elm 20" N. 37° E. 50 lks., Hickory 8" S. 25° W. 11½ lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1963: Wilkins & Wheaton Engr. Co.; Found tile in North, South, East and West fence line, 6" below surface:

1998: Found 3" round tile, top broken off, 6" below surface with stones around 567'± West of center line of Willow Swamp Drain in East and West fence line.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
6-11-1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-05: Southeast corner, Section 11, T. 3 S., R. 9 W., ratified June 11, 1998 by the Kalamazoo County Remonumentation Program Peer Group and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round clay tile with the top broken off. Tile was set by F. Hodgman in 1883 Remonumentation survey. Placed remonumentation sleeve over tile.

PK Nail in East Side	10" Maple	North	27.02'
PK Nail in West Side	12" Hickory	N. 52° E.	46.15'
PK Nail in South Side	22" Butternut	S. 55° E.	23.52'
PK Nail in West Side	6" Cottonwood (Double)	S. 40° W.	25.25'

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date 9-2-98