

**SURVEY &
REMONUMENTATION**

1
2
OCT 06 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Climax Township

KALAMAZOO
(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>3S</u> R <u>9W</u>	<u>L-05</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

LIBER 2 PAGE 161
97 JUL 29 AM 11 00
STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
Clerk - Register
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on May 23, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP 6-19-1997**

A. Description of original monument and accessories and/or subsequent restoration:

1826: United States Government Surveyors; Set 1/4 Section Post.

Ironwood 8" North 17° West 9 Lks
White Ash 13" South 32° East 6 1/2 Lks

1876: F. Hodgman, County Surveyor; "Found stake from one living witness. Set new stake."

1883: F. Hodgman, County Surveyor; "Bored 3 feet. Filled bottom with stone and put 2 foot earthen post over. Elm 20" North 51° West, 22 1/2 Lks."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997: Found 3" round tiles (2) side by side in a pile of stones. Offset both tile and dug to 3 1/2' finding large stones all the way to the bottom of hole. Replaced stones and placed tiles over stones. Note: Westerly tile fit "stone hole" best as well as there being 2, 1/2" x 18" irons found along side Westerly tile. One on the North Side and one on the South Side.

Nail in South Side 14" Ash South 75° East 20.29'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-05 South 1/4 Post Section 12, T. 3 S., R. 9 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on June 19, 1997 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found two, one-foot sections of 3" round tiles with "x" on top and stones as set in 1883 remonumentation survey by F. Hodgman, County Surveyor. Replaced tile as in "B" above and placed remonumentation sleeve over top section of tile.

Exist. Nail in East Side 15" Ash North 20° East 29.30'
PK Nail over exist. Nail in West Side 22" Ash (Double) South 12° East 10.77'
PK Nail in East Side 14" Oak South 40° West 30.01'
PK Nail in North Side 4" Ash North 50° West 15.42'

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date 7-28-97