

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

93 NOV 29 PM 2 22

For corners in

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
Climax Township		
1. Public Land Survey	T <u>3</u> S R <u>9</u> W	<u>L-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

James P. Pump
CLERK-REGISTER

1 PG 1042

LIBER

Register of Deeds Stamp & File Number

I, John G. Kester, in a field survey on August 12, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established; monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Corner Post established by U S Government Deputy Surveyor Robert Clark, 1826, Accessories: W Ash 8 N27¹/₂E 1.54, Willow 6 n53W 40. Survey by F. Hodgeman, 1869, Found about 12" of Original Stake in Swamp from Stump and Roots of two witnesses. Set a large Willow Stake and witnessed. Remonumentation by F. Hodgeman, 1883, Found Original Stake of U S Survey still remaining in the ground and Bearing Trees of resurvey by me in 1869 standing in swamp. Planted in the old Stake Hole 3' Earthen Post. Accessories: Elm 3 S85E 42, Maple 8 N5¹/₂W 88.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original Corner and Accessories not recovered. Found Solid Clay Tile with Cap (top 1' with Cap broken off) 5' below road surface, witnesses gone, as called for by 1883 Remonumentation by F. Hodgeman.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
9-16-93

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9, S¹/₄ Corner Section 24, T3S-R9W, Ratified by Kalamazoo County Remonumentation Program Peer Group on September 16, 1993. Found Solid Clay Tile with Cap (top 1' with Cap broken off) and is accepted as a careful and faithful perpetuation of the Original Corners position. Set top 1' of Solid Clay Tile with Cap over lower portion of Solid Clay Tile. Placed 30" Harrison Monument above Solid Clay Tile with Cap and placed Monument Box over Corner.

- Set P.K. Nail in 6" Maple N20E 38.73'
- Set P.K. Nail in 7" Ash N5W 37.39'
- Set P.K. Nail in 10" Ash S45E 38.92'
- Set P.K. Nail in 4" Ash S40W 42.04'

Signed by *John G. Kester*

Date 11-29-93

Surveyor's Michigan License No. 16046
Kalamazoo County Road Commission