

**SURVEY &  
REMONUMENTATION**

OCT 06 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Climax Township

KALAMAZOO  
(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>3S</u> R <u>9W</u>	M-06
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER 2 PAGE 163

CLERK - REGISTER

*Annally Brown*

'97 JUL 29 AM 11 00

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert E. Snell, in a field survey on May 27, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

1825: United States Government Surveyors; Set 1/4 Section Post.

Beech 12" South 30 1/2° West 32 Lks  
Beech 6" North 48° West 8 Lks

1883: F. Hodgman, County Surveyor; "Found stake standing and old stake hole 1 Lks South. Bored 3 feet in the old stake hole. Put stone and broken brick in the bottom and 2 foot earthen post over. Hickory 8", South 77° East, 218 Lks, Cherry 8", North 80 1/2° West, 287 Lks."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997: Found 3" round tile with 4, 1/2 x 18" irons around it down about 3". Tile was leaning slightly to the South. Dug down 1 1/2' and found tile broken. Small stones around tile. Placed sleeve over broken tile with concrete around and top piece of tile in sleeve. Placed monument box over sleeve about 2 1/2" below surface of gravel road. Found pointed stone South 14.42' (Government Job-22 Lks=14.52').

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
6-19-1997

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-06 East 1/4 Post Section 13, T. 3 S., R. 9 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on June 19, 1997 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile as placed in 1883 remonumentation survey by F. Hodgman, County Surveyor. (See "B" above) Placed remonumentation sleeve over tile and monument box over sleeve.

PK Nail in North Side 15" Ash South 38° East 44.22'  
PK Nail in East Side 30" W. Cherry South 32.48'  
PK Nail in North Side 12" W. Cherry South 78° West 50.66'  
PK Nail in East Side (over Exist. Nail) 28" Ash North 02° West 18.75'

Signed by *Robert E. Snell*  
Surveyor's Michigan License No. 9734

Date 7-28-97