

SURVEY &
REMONUMENTATION

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

'93 NOV 29 PM 2 22

For corners in

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
Climax Township		
1. Public Land Survey	T 3 S R 9 W	M-9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

James J. [Signature]
CLERK-REGISTER

LIBER 1 PG 1043

Register of Deeds Stamp & File Number

I, John G. Kester, in a field survey on August 12, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
Corner Post established by U S Government Deputy Surveyor John Mullett, 1825, Accessories: Beech 6 S47W 24, Beech 5 N36W 26.
Survey by F. Hodgeman, 1869, Found about 3" of Original Stake from Stump of one witness. Set Slate Stone 18" long with point at surface and smaller Stone around. Accessories: Black Ash 15 S29E 73, Elm 15 S49 1/2 W 59.
Remonumentation by F. Hodgeman, 1883, Found Stake and Stone of former survey by myself and 2 bearing trees standing. Bored 3' in Stake Hole beside Stone, filled bottom with broken Brick and set 2' Earthen Post on top.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Original Corner and Accessories not recovered.
Found Solid Clay Tile with X on top and Stone around 36" below road surface as called for in 1883 Remonumentation by F. Hodgeman.

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
9-16-93**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-9, Corner of Sections 24 & 25, T3S-R9W, Ratified by Kalamazoo County Remonumentation Program Peer Group on September 16, 1993. Found Solid Clay Tile with X on top and Stone around and is accepted as a careful and faithful perpetuation of the Original Corners position. Placed 20" Harrison Monument above Solid Clay Tile with X on top and placed Monument Box over Corner.
S.W. Cor Sec 19, T3S-R8W, Harrison Monument over Tile in Monument Box South 13.06'
Center North End 30" CMP N5W 20.74'
Center/Top Project Marker S5E 32.04'
Set P.K. Nail in 11" Ash S50E 66.88'

Signed by *John G. Kester* Date 11-29-93
Surveyor's Michigan License No. 16046
Kalamazoo County Road Commission