

'94 APR 28 AM 9 12

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KALAMAZOO

(County)

Sec. 25, Climax Twp.

1. Public Land Survey

Located In:

Corner Code #

T 3 S R 9 W

M-11

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section

3. Miscellaneous

Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

*James J. [Signature]*

CLERK-REGISTER

LIBER 1 PG 1145

Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on March 7, 19 94

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1825-Original corner established by U.S. Government Survey-Set Post, corner to Section 25 & 36

Wh. oak 12" South 29½° West 44 Lks

Wh. Oak 12" North 36½° West 96 Lks

1869-F.Hodgeman, County Surveyor-Set stake from stump of one witness. Over the stake set an oblong stone, point up, with small stones and brick around-notch cut in top

Wh. Oak 18" South 38°-10' East 29 Lks

Y. Oak 6" North 19°-05' West 13 Lks

1883-F.Hodgeman, County Survey-found stone of resurvey with old stake under it and Bearing Trees of resurvey staking. Bored 3' in stake hole, filled the bottom with broken brick and put

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: 2½' earthen post over with stone around.

Found 1/2' of 3" clay tile over brick by 1869 witness of Y. Oak.

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
 3-17-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11 Southeast corner Section 25, T. 3 S., R. 9 W., ratified by Kalamazoo County Remonumentation Program Peer Group on March 17, 1994. Found ½' of 3" round tile over brick as called for in 1883 remonumentation survey by F.Hodgeman and is accepted as a careful and faithful perpetuation of the original corner's position. Placed 20" Harrison monument over brick.

PK Nail in Southeast Side	42" Oak	North 20° West	5.97'
PK Nail in South Side	Triple 18" Oak	East	42.08'
PK Nail in South Side	Telephone Pole Fence Post	South 32° West	68.72'
PK Nail in South Side	14" Oak	North 60° West	23.20'
Iron in CL Road		South	16.4'

Signed by Robert E. Snell

Date 4-27-94

Surveyor's Michigan License No. 9734