

**SURVEY &
REMONUMENTATION**

FEB 18 1994

LIBER 1 PG 1080

COMMISSION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **PAVILION TWP.**

KALAMAZOO
(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>3S</u> R <u>10W</u>	<u>A-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
94 JUN 20 PM 3 09
Clerk-Register
[Signature]

Register of Deeds Stamp & File Number

Allen H. McMachen a field survey on December 18, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1888 - F. Hodgeman C.S. placed Clay Tile post during official Township Remonumentation.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Clay Tile at surface of ground between existing tree roots.

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
12-30-93**



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found Clay Tile is accepted as a careful and faithful perpetuation of the original corner. Placed Standard Sleeve over existing Tile, accessories:

Nail & Tab in East face	14"	Oak	N. 05 deg. E.	27.75'
Nail in West face	Tri.	Maple	N. 40 deg. E.	29.92'
Nail in North face	8"	Hickory	S. 82 deg. E.	35.50'
Nail in East face	42"	Maple	SOUTH	6.73'

Signed by *Allen H. McMachen* Date 1/19/94
Surveyor's Michigan License No. 16935