

SURVEY & REMONUMENTATION

FEB 26 1998

7-
2-

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIDER

2 PAGE 277

For corners in Pavilion Twp.

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 3S R 10W	B-02
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
.97 DEC 29 AM 10 55
Clerk - Register
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on Oct. 16, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1	6											
2		5		4		3		2		1		
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This corner not set by original Government Surveyors.

1872: S. Hodgman, Deputy Land Surveyor; Center 1/4 post "stake at intersection of 1/4 lines marked Elm 15" S. 40° E. 11 lks., Elm 15" N. 80° W. 13 lks."

1881: E. Strong, County Surveyor; found all right as in record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Circa 1920: Wilkins & Wheaton Engr. Co.; from Section notes, placed tile from witnesses. stake gone.

Maple	S. 04° E.	32.85'	Hickory	S. 80° W.	27.5'
Elm 30"	S. 40° E.	6.7'			

1947: Wilkins & Wheaton Engr. Co.; found tile at center 1/4.

1996: Found 3" round tile with "x" on top.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
12/18/97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-02: Center 1/4 post, Section 6, T. 3 S., R. 10 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on December 18, 1997 and is accepted as a careful and faithful perpetuation of the position established in 1872 by S. Hodgman, Deputy Land Surveyor. This corner not established by original Government Surveyors. Found 3" round tile believed to be set by Glen C. Wheaton, Circa 1920. Set remonumentation sleeve over tile.

PK Nail in East Side	18" W. Cherry	S. 02° W.	13.90'
PK Nail in North Side	32" Hickory	S. 87° W.	27.75'
PK Nail in North Side	16" Oak	S. 85° E.	40.25'
In line with	fence to South		

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date 12-23-97